BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK :PACKAGE-9

DRAFT TENDER SCHEDULE

Sl. No.	Description of Work	Unit	Quantity	Rate in Figures	Rate in Words
1	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, roads drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up lift 1.5, excavated surface leveled and neatly dressed disposed earth to be leveled after breaking of clods and neatly dressed as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	2210.59	166.42	Rupees One Hundred Sixty Six and Forty Two Paise Only
2	Removing B.S.slab of Drain and stacking as per the directions of the Engineer-in-charge of the work .	Sqm	769.86	65.72	Rupees Sixty Five and Seventy Two Paise Only
3	Removing and refixing stone slabs of drains and pointing in CM (1:3) as per the directions of the Engineer-in-charge of the work .	Sqm	130.48	80.56	Rupees Eighty and Fifty Six Paise Only
4	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete as per the directions of the Engineer-in-charge of the work .	Sqm	21.75	665.68	Rupees Six Hundred Sixty Five and Sixty Eight Paise Only
5	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete as per the directions of the Engineer-in-charge of the work .	Sqm	746.94	825.74	Rupees Eight Hundred Twenty Five and Seventy Four Paise Only
6	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	8.49	86.92	Rupees Eighty Six and Ninety Two Paise Only
7	Excavation in Soil using Hydraulic Excavator CK 90 and Tippers with Disposal KSRRB M300-14. Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location and complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	354.81	48.76	Rupees Forty Eight and Seventy Six Paise Only

8	Lead for disposal of earth shall be payable at Carriage rates (Lead & Lift) by mechanical means including loading and unloading up to 15kms as per the directions of the Engineer-in-charge of the work .	Cum	2791.29	112.78	Rupees One Hundred Twelve and Seventy Eight Paise Only
9	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications (Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) and as per the directions of the Engineer-in-charge of the work .	Cum	591.35	320.12	Rupees Three Hundred Twenty and Twelve Paise Only
10	Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	2365.38	5.30	Rupees Five and Thirty Paise Only
11	Providing,laying, spreading and compacting crushed stone aggregates of granite/trap/ basalt to wet mix macadam specification including pre mixing the Material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density. complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	599.83	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
12	Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by manual means without disturbing the base and stacking of the debris materials including cost of all labour charges complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	154.44	60.42	Rupees Sixty and Forty Two Paise Only
13	Cleaning the existing WBM Road surface including removing of binding materials and other foreign matter with wire brushes and small picks sweeping with brooms or soft brushes and finally dusting with old gunny bags and bar or compressed air to receive bituminous treatment including cost of all materials, labhour, HOM of machineries complet as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	2556.71	13.78	Rupees Thirteen and Seventy Eight Paise Only
14	Providing and applying tack coat using 80/100 grade bitumen (VG 10) on granular base such as WBM surface hot bitumen primed at 4kg per 10 sqm heating bitumen in boiler with spray set (Excluding cleaning of Road surface) inlcuding cost of all materials, labhour, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	2556.71	19.08	Rupees Nineteen and Eight Paise Only

15	Providing and laying bituminous macadam on prepared surface with crushed coarse as per design mix formula for base / binding courseincluding loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant,transporting the mixed material in tipper to paver and laying mixed materials, with paver finisher to the required level and grade,rolling by power roller to achieve the desired density,but excluding cost of primer/tack coat including lead,lift and cost of all materials,labour,HOM of machineries complete as per specification and as per the directions of the Engineer-in-charge of the work .	Cum	134.23	5733.54	Rupees Five Thousand Seven Hundred Thirty Three and Fifty Four Paise Only
16	Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	26809.48	3.18	Rupees Three and Eighteen Paise Only
17	Providing and applying tack coat using 80/100 grade bitumen(VG10) in boiler fitted with spray set distributor at the rate of 0.20kg per sqm on the existing prepared bituminous surface cleaned with mechanical broom. complete as per specification and as per the directions of the Engineer-in-charge of the work .	Sqm	26809.48	9.54	Rupees Nine and Fifty Four Paise Only
18	Providing and laying bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler,transporting the hot mix to work site,laying with a paver finisher to the required grade, level and alignment,rolling with smooth wheeled,vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.500.9 complete in all respects complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	1179.62	9012.12	Rupees Nine Thousand Twelve and Twelve Paise Only
19	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	516.53	542.72	Rupees Five Hundred Forty Two and Seventy Two Paise Only

20	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specification and as per the directions of the Engineer-in-charge of the work .	Cum	217.40	827.86	Rupees Eight Hundred Twenty Seven and Eighty Six Paise Only
21	Construction of dry lean cement concrete mix CC1:5:10 with OPC cement @160Kgs, with 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum Sub- base over a prepared sub-grade with (coarse and fine aggregate conforming to IS: 383) aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, cement content not to be less than 160 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Cum	217.40	3986.66	Rupees Three Thousand Nine Hundred Eighty Six and Sixty Six Paise Only
22	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications and as per the directions of the	Cum	229.11	6217.96	Rupees Six Thousand Two Hundred Seventeen and Ninety Six Paise Only

23	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Conrete Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms and 2Ltr of Primer per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and as per the directions of the Engineer-in-charge of the work .	Sqm	31.29	685.82	Rupees Six Hundred Eighty Five and Eighty Two Paise Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾ
ಬೃ.ಬೆ.ಮ.ಪಾ, ಬೆಂಗಳೂರು

"DTS Approved"

CE (Y)